## **REQUEST FOR PURCHASE**

Project Number: 2345645

PRKR154
DATE ORIGINATED
06/20/13

	This Meter Station
SITE:	Parker
DAY NEEDED:	
DELIVER TO:	Address
REQUESTED BY:	
PHONE:	
APPROVED BY:	
PHONE:	

	F	PHONE:		
QUANTITY	ITEM#	UNIT	ITEM DESCRIPTION	UNIT PRICE
1	4	FT	PIPE - 20", 0.500" WT, ERW/DSAW, BE, API 5L PSL-2, X60, BARE	
8	6	FT	PIPE - 16", 0.500" WT, DSAW, BE, API 5L PSL2, X52, COATED WITH 14 - 16 MILS FBE	
29	9	FT	PIPE - 10", 0.365" WT, ERW/SMLS, BE, API 5L PSL-2, X52, BARE	
1	27	EA	TEE, REDUCING - 12", 0.375" WT x 6", 0.280" WT, BW, MSS-SP-75, Y52, PER ASME B16.9	
1	71		PLUG, HEXHEAD, 1", 3000#, MNPT, ASTM A105, PER ASME B16.11	
1	72		PLUG, HEXHEAD, 3/4", 3000#, MNPT, ASTM A105, PER ASME B16.11	
1	73		PLUG, HEXHEAD, 1/2", 3000#, MNPT, ASTM A105, PER ASME B16.11	
1	94	ΕΛ	GASKET, SPIRAL WOUND - 1 1/2", ANSI 600, RF, FLEXITALLIC, STYLE CGI OR EQUAL, 304 SS WINDING WITH GRAPHITE FILLER, 304 SS OUTER & INNER RING, 1/8" THK, FOR ASME B16.5 FLANGE	
	-			

-		
-		